

Tabulizer

version 6.x

Add to your Wordpress site professionally looking tables and graphs with just a few clicks.



Developed by Alterora

<http://www.tabulizer.com>

Table of contents

Installation.....	4
How to update or upgrade Tabulizer.....	4
How to uninstall Tabulizer.....	4
How to Use.....	4
Before you start: Check your permissions!.....	4
Creating a table with Tabulizer.....	6
Editing a table with ReTabulizer.....	9
Basic Concepts: What is a rule, a ruleset and a ruleset archive.....	11
Overview.....	11
What is a rule.....	13
What is a ruleset.....	28
What is a ruleset archive.....	29
Preview ruleset styling.....	29
Automatically create and edit CSS skeleton for rulesets.....	29
Where are the files located.....	31
Example: Creating a ruleset from scratch.....	32
Setting the requirements.....	32
Creating the rules.....	32
Defining the CSS Selectors.....	33
Putting it all together.....	35
Naming conventions.....	36
Taking our example to the next level.....	36
Calculating automatically the total sum.....	36
Format the cells as currency.....	36
Using Autospan for our table title.....	37
Putting it all together.....	38
Importing ruleset archives	41
Request a custom-made ruleset for you.....	41
Copying tables from another application.....	43
Importing tables directly from an Excel document	43
Exporting tables and data from an Excel document	44
Exporting tables from a Word document.....	45
Data Sources for tables with dynamic content	46
How to create a new data source.....	46
Add more flexibility with data source variable parameters.....	48
Convert your tables into graphs.....	50
Create a graph ruleset – Basic Example.....	52
Using more options to adjust your graph.....	56
User Preferences.....	58
Status – Tabulizer, Wordpress and System Information.....	59
Troubleshooting common issues.....	60
Issue #1: Unable to insert the produced HTML code into the article.....	60
Issue #2: The produced table does not appear as expected.....	60
Issue #3: Rulesets are missing or have different rules and attributes	60
Issue #4: Unable to import rulesets, write files or create folders.....	61
Issue #5: Internal Server Error (500).....	61
Issue #6: “The number of columns must be the same on each row” error message.....	61
Issue #7: Magic quotes are on, causing slashes to be added automatically in front of double	

quotes (\").....	61
Issue #8: HTML links and other elements are removed or set to “undefined” when I click the insert button.....	62
Issue #9: Strict error reporting (E_STRICT) is causing error messages similar to “Strict Standards: Only variables should be assigned by reference in ...”.....	62
Issue #10: Fix for “datatables warning (table id): Requested unknown parameter X from the data source for row Y”.....	62
Issue #11: Fix for “MySQL server has gone away”.....	62
Getting more help and updates.....	63

Installation

The Tabulizer application can be easily installed on your Wordpress site, like any other plugin. More specifically, you need to do the following steps:

- 1) Unzip the file tabulizer_UNZIPME.zip and locate the plugin installation file tabulizer.zip
- 2) Login as administrator to your Wordpress site and go to menu Plugins and click on the "Add New". Then click on the "Upload Plugin" button, select the tabulizer.zip file you extracted in the previous step and click on the "Install Now" button.
- 3) Activate the installed plugin.

Please note that if your server is not permitting file uploads with file size larger then 2MB, you can simply unzip the tabulizer.zip file and copy the extracted subfolder “tabulizer” to *{wordpress root directory}/wp-content/plugins* folder.

How to update or upgrade Tabulizer

To update Tabulizer or upgrade from a previous version, you need to do the following steps:

- Unzip the file tabulizer_UNZIPME.zip
- Copy the subfolder “tabulizer” to *{wordpress root directory}/wp-content/plugins* folder, thus overwriting the existing files.

Do not de-activate the plugin during the upgrade, because all existing data sources will be deleted.

Nevertheless, there are cases in which the new Tabulizer version will contained some modifications in the database strcuture and the de-activation and re-activation if the plugin will be necessary for these changes to take effect. If that's the case, please export your data sources first (i.e. make of back-up) and when the new version is installed import them in order to restore them.

How to uninstall Tabulizer

Should you need to uninstall the Tabulizer application, simply de-activate the Tabulizer plugin and then remove the *{wordpress root directory}/wp-content/plugins/tabulizer* folder.

How to Use

Before you start: Check your permissions!


Starting from Tabulizer version 3.0, you need to have enough permissions to execute a specific group of tasks. More specifically, any Wordpress user must belong to a user group that is allowed to:

- View Rulesets:
- Create and Edit Rulesets:
- Import Rulesets:
- Export Rulesets:

- View Data Sources:
- Create and Edit Data Sources:
- Import Data Sources:
- Export Data Sources:
- Import Data Files:

This was done for security purposes and when you install Tabulizer only the Administrators have access to these operations. If you want to add another group of users you have to do this manually, by changing the corresponding permission parameters.

For instance, if you want to allow editor to be able to import data from an Excel file click on the **Permissions** link, under the **Tabulizer** side menu, and then click with your mouse the “Author” use group. Keep the control button pressed (Ctrl), if you want to select more than one user groups. See figure below.





Note the the permissions have been implemented internally using the Wordpress notion of capabilities and roles, so any other WP plugin that can modify these capabilities will affect Tabulizer's permissions.

Creating a table with Tabulizer


Adding tables with Tabulizer in your Wordpress posts is very easy. When you are editing your post click on the **Tabulize!** button to invoke Tabulizer's popup window.

If you are using Wordpress 5.x or newer, most likely you are using the Gutenberg editor, which relies on "blocks" to construct the content of the post/page. Unlike the classic editor (i.e. TinyMCE) where all content is contained in a single area, Gutenberg is using various block types that are associated with a different type of content. Tabulizer has its own block type that you can find under the "formatting" category, as shown in the images below.



As you can see, you need to first insert a new block of type "Tabulizer" and then click on the "Tabulize" toolbar button (for creating static tables) or to the "Insert Data Source" toolbar button (for displaying dynamic tables).

With the old "classic" WordPress editor the things are more straightforward. Once you edit the post, or the page, the editor's toolbar will contain 3 new buttons labelled "Tabulize!", "ReTabulize" and "Data Sources", as shown below:




For instance, let's assume you want to create a new (static) table. You should click on the "Tabulize" button and wait for the popup window to appear.

In the popup window type in the **Input Text** box the table data according to the following rules:

- 1) Each line corresponds to a table row
- 2) Each column is separated with the **Column Separator** character that can be a comma (,) or a few other available characters. If the column value contains the separator character, use double or single quotes as **text enclosure**. So, for instance all the lines below are acceptable:

- one,two,three (*column separator: comma, text enclosure: none or double quotes*)
- one,"two",three (*column separator: comma, text enclosure: double quotes*)



- one,"two,two",three (*column separator: comma, text enclosure: double quotes*)
- one;two;three (*column separator: semicolon, text enclosure: none or double quotes*)
- one;two,two;three (*column separator: semicolon, text enclosure: none or double quotes*)

- 3) The number of columns on each row must be the same. Since the number of columns is specified by the number of column separators, it is implied the every column must have the same number of column separators (e.g. commas). We do not count column separators that are text enclosed. Here is a valid input:

1,2,3,4

5,6,7,8

79,10,11,12

There are 3 rows and 4 columns on each row, using comma (,) as our column separator. Obviously, the following formula applies:

of column separators = # columns – 1

In our example, the number of commas (column separators) on each line (row) is 3, since we have 4 columns ($3 = 4 - 1$).

Rule #3 tells us that the number of columns on each row must be the same, otherwise an error message will appear when we try to convert the input text into a table:

“Please correct the following errors before you try to convert the input text again:

1. The number of columns must be the same on each row. Please make sure the column separator is not used in the field value of any column. Hint: Row(s) 1 have 3 columns, while row 2 has 2 columns.”

The hint tells us where the column inconsistency lies. Here is the input that caused the above error message:

1,2,3 ← 3 columns

4,5 ← 2 columns

7,8,9 ← 3 columns

As you can see row 2 has only one comma, therefore only two columns, while row 1 and row 3 have two commas, therefore 3 columns. To solve this problem, you need to add an extra column in row 2 by adding the missing comma. Note, that the place where you put the missing comma will specify the place of the missing empty cell. For instance, all the following inputs are valid:

1,2,3	1,2,3	1,2,3
4,5,,	4,,5	,4,5
7,8,9	7,8,9	7,8,9

and they will create the following tables:

1	2	3
4	5	
6	7	8

1	2	3
4		5
7	8	9

1	2	3
	4	5
7	8	9

Starting from version 3.0 Tabulizer applies by default “loose” column consistency, meaning that it will try to append automatically the missing column separators at the end of each (inconsistent) line, if any. You can enforce strict column consistency by setting the **Column consistency** field to **Strict**.

Once you have typed your input text, the next step is to select the desired **Ruleset**. You can filter the list of the available rulesets by selecting a specific **Archive**. A ruleset is a table template, while an archive contains one or more rulesets.

Click to import data directly from an Excel file [Beta]

Input Text:

```
1,2,3
4,5,6
7,8,9
```

Type here or past your table data in plain text format

Output HTML Code:

```
<tr class="tabrow" "><td class="tabcol">4,5,6</td></tr>
<tr class="tabrow" "><td class="tabcol">7,8,9</td></tr>
</table>
```

Column Separator: Asterisk (*)

Text enclosure : Single Quotes (')

Column consistency: Loose - Add missing columns

Archive: Elemental 1 Grey

Ruleset Name: Elemental 1 Grey Plain Box - With border

Convert **Insert** **Close**

Simple table border

When you are ready click on the **Convert** button. If there were no errors, the produced HTML table will appear in the **Output HTML Code** box. Review the code and then click on the **Insert** button to add the table into your article.

Important! First select the desired ruleset and then click the convert button.

Right before the produced table will be a Tabulizer directive, similar to `{tabulizer:include style[gr.alterora.elemental_1_grey.css] id[tan_gmtYlaDYk]}`. This directive is invisible to the visitors of your site and it is used internally by Tabulizer to know which action to take (e.g. include as CSS file, convert the table to graph, etc).

Editing a table with ReTabulizer

Sometimes, you want to edit an existing table. You can change the values of the cells, or simply the style of the table. Starting from version 3.0 you can click anywhere inside the table you want to edit and then click on the **Re-Tabulize!** button. It will popup the same window as if you had clicked on the **Tabulize!** Button, but with a difference: the Input Text is filled with the tabular data in plain text format.

One of the uses for ReTabulizer is to apply a new ruleset to an existing table. So, let's say you have an existing table and you want to beautify it with a new sexy ruleset. Here is what you should do:

1. Click anywhere inside the table (preferably in the middle of the table) and you make sure that the cursor is inside the table cells.
2. Click on the **Re-Tabulize!** button to open the Tabulizer window. The **Input Box** should have the contents of the table as plain text. Only the cell values are copied, but if they contain HTML code, it will be preserved (e.g. `<span class="emphatic">Top Plays</span>`).
3. Select the desired ruleset from the available list.
4. Click on the **Convert** button and then the **Insert** button to add the table with the new ruleset in the original content.

Upload/Insert

HTML

Basic Concepts: What is a rule, a ruleset and a ruleset archive

Overview

The Tabulizer component allows you to create sets of rules (i.e. rulesets) that specify how to style specific elements of a given table, do simple arithmetic calculations or even merge automatically neighboring cells. For instance, you can add a rule that will change the background color of the first table row or add another rule that will calculate automatically the sum of all the values of certain rows or columns. You can set as many rules as you want and these rules can be combined together giving you unlimited possibilities.

For better flexibility, the styling rules only specify the CSS selector that will be applied to the table element (row/column/cell), while the definition of the CSS selector is done in a separate CSS file. This means that you can use for your rules CSS selectors that are already defined elsewhere (e.g. your template's CSS files) and if you decide to change the CSS selector definition in the future, it's only a matter of editing a regular CSS file.

Let's see an example to illustrate these ideas. Let's assume that we have a sports site and you want to display after each matchday the results and the current standings of each major sports league in your country. This apparently involves the creation of many tables and you want to do that fast with a consistent feel and look. Tabulizer fits these needs perfectly. Using the Tabulizer you create a set of rules for each table you want to add or update repeatedly. For instance, the ruleset for the standings of the national basketball league could contain the following styling rules:

- A rule to make the background color of the first row unique and the font weight bold, as the first row contains the column headers for the rest of the table.
- A rule to make the background of the first column different than the rest of the table and the font weight bold, as the first column contains the names of the teams.
- A rule to make the table more readable, so the even rows will have a slightly different background color than the odd ones.

In order these rules to be effective, we need at least two types of file:

1. One XML file to store the definition of the rules/how to apply the CSS selectors on each element of the table
2. One CSS file to store the definition of the CSS selectors/what properties should have each CSS selector.

In our example these files might look like this:
1) XML file (*nbl.xml*):

```
<ruleset name="ruleset_nbl" title="National Basketball League" suffix="ruleset_nbl" style="nbl.css" >
<rule element="row" range="1" style="nbl_header"></rule>
<rule element="column" range="1" style="nbl_teams"></rule>
<rule element="row" range="EVEN" style="row_even"></rule>
</ruleset>
```

2) CSS file (*nbl.css*):

```
/* first row */
.nbl_header { background-color: #FF9900; font-weight: bold; }
/* first column */
```

```
.nbl_teams { background-color: #FFCC00; font-weight: bold; }
/* even rows */
.row_even { background-color: #f5f5f5; }
/* take special care of the cell that is part of the first row and the first column */
tr.nbl_header td.nbl_teams { background-color: #FF9900; font-weight: bold; }
/* add a table border */
.tabtable-ruleset_nbl { border: 1px dotted #030303; }
```

For input text:

```
Teams,Points
Black Bears,89
Brave Fishes,87
White Cats,86
Proud Lions,84
Southern Cougars,79
```

The resulting table would look like this:

Teams	Points
Black Bears	89
Brave Fishes	87
White Cats	86
Proud Lions	84
Southern Cougars	79

Table: Visual Display

Table: HTML Source Code

```
<table class="tabtable-ruleset_nbl">
<tr class="tabrow nbl_header">
<td class="tabcol nbl_teams">Teams</td><td class="tabcol
">Points</td>
</tr>
<tr class="tabrow row_even">
<td class="tabcol nbl_teams">Black Bears</td><td
class="tabcol ">89</td>
</tr>
<tr class="tabrow ">
```

```

<td class="tabcol nbl_teams">Brave Fishes</td><td
class="tabcol ">87</td>
</tr>
<tr class="tabrow row_even">
<td class="tabcol nbl_teams">White Cats</td><td
class="tabcol ">86</td>
</tr>
<tr class="tabrow ">
<td class="tabcol nbl_teams">Proud Lions</td><td
class="tabcol ">84</td>
</tr>
<tr class="tabrow row_even">
<td class="tabcol nbl_teams">Southern Cougars</td><td
class="tabcol ">79</td>
</tr>
</table>

```

The XML file is created and updated automatically by the Tabulizer component, even though it is possible to edit it manually using a standard text editor (like Notepad) if you are familiar with the XML format. The recommended option is to use exclusively the Tabulizer component to create and edit the resulting XML files, because not only it is more convenient but also more robust and error-free thanks to all the validation tools that come with. All the XML files containing the rulesets are located in the */templates/tabulizer/rules* directory.

The CSS file can be edited via the Tabulizer component as well, or it can be edited manually using a standard text editor, or a specialized CSS editor. The Tabulizer component has built-in functionality that allows you to create the skeleton CSS file contents, once the rules has been set. Not all CSS selectors need to be defined. Only those you are interested in should be defined from the very beginning and the rest could be defined later on or never. The important thing to remember is that all CSS files that contain CSS selectors for the rules you want to use, must be included in your Wordpress site. This is done automatically by the Tabulizer plugin.

You can familiarize yourself with the concept of rulesets by examining some existing ruleset archives to see how they are constructed. For a detailed description of the attributes for rules, rulesets and archives read the following paragraphs.

What is a rule

A rule is an instruction on how to apply a specific CSS selector to a table element or on how to format a cell or calculate its value from neighboring cells. Note, there are many other “actions” that a rule can take, including replacing one text with another, converting a regular table into a graph, adding responsive behavior and many more. For the sake of simplicity we will stick with the basic ones. When you define a new rule you have to specify the following properties/fields:

1. **Element:** This is the type of elements to which the rule applies and it can be:
 - *row*: indicates a table row

- *column*: indicates a table column
- *cell*: indicates a table cell
- *table*: indicates the whole table

2. Range:

The value of this field gives the range of the selected elements to which the rule applies, and therefore it depends on the element type.

Starting from version 4.0, as acceptable integer value is consider the L<integer value> annotation that indicates the X element from the end. So, for instance if you have a table with 10 rows, the L3 row would be the 8th (L1 → 10th, L2 → 9th, L3 → 8th, etc).

Also, you can combine multiple range selections in a single assignment, giving you more control over the final (combined) range selection. More specifically, you can:

- unify multiple range selection, using the symbol ; as your range separator
- filter any existing element selection using the # symbol as your filter flag
- exclude elements from any existing selection using the ^ symbol as your exclusion flag

For instance, in a table with 10 rows, the combined row range selection <3;>=5#2-4;4-6^3-5 is interpreted as follows:

Subrange #1: < 3 select row ids less than 3 => 1,2

Subrange #2: >=5#2-4;4-6^3-5 select rows ids greater or equal to 5 => rows 5,6,7,8,9,10.

Filter the results so only row ids that are between 2 and 4 are kept => no rows

Subrange #3: 4-6^3-5 select row ids between 4 and 6. From them, exclude row ids between 3 and 5 => 6

United all previous results 1,2 + 6 => 1,2,6

If the type is **ROW** or **COLUMN**, this can be:

- *<integer value>*: An integer value which indicates which row or column you are referring to. Example value: 1
- *<integer value from>-<integer value to>*: A range of integers which indicates the range of rows or columns you are referring to. Example value: 1-3
- *<integer value>,<integer value>,...,<integer value>*: A comma separated list of integers, indicating the specific rows/columns you are referring to. Example value: 1,3,5
- *> <integer value from>*: A lower limit which indicates the range of rows or columns you are referring to. Example value: > 3
- *>= <integer value from>*: Same as above, but instead of "greater than" we use for comparison "greater than or equal". Example value: >= 3
- *< <integer value to>*: An upper limit which indicates the range of rows or columns you are referring to. Example value: < 3
- *<= <integer value to>*: Same as above, but instead of "less than" we use for comparison "less than or equal". Example value: <= 3
- *FIRST <integer value>*: the integer value indicates the first X rows/columns you are referring to. Example value: FIRST 3
- *LAST <integer value>*: the integer value indicates the last X rows/columns you are referring to. Example value: LAST 3
- *MOD <integer value>*: the integer value indicates the modulo X rows/columns you are referring to. Example value: MOD 3
- *MOD<integer value>[LIMIT SUBRANGE]*: same as the previous case, but you limit

the modulo operation to a specific subrange. See below for acceptable values for LIMIT RANGE. Example value: *MOD 3 [>1]*

- *ODD*: indicates the the rule applies only to odd rows/columns. Example value: *ODD*
- *ODD [LIMIT SUBRANGE]*: same as the previous case, but you limit the modulo operation to a specific subrange. Example value: *ODD [>3]*
- *EVEN*: indicates the the rule applies only to even rows/columns. Example value: *EVEN*
- *EVEN [LIMIT SUBRANGE]*: same as the previous case, but you limit the modulo operation to a specific subrange. Example value: *EVEN [>3]*
- *ALL*: all rows/columns. This is equivalent to range 1-L1. Example value: *ALL*
- *SAME <base64 encoded text value>*: the row/column must contain at least one cell whose value is equal to the text value for the rule to apply. You can also search part of the row/column using the optional column/row specifier that is described later on. Example value: *SAME V2lubmVy*
- *SAMEi <base64 encoded text value>*: same as above but case insensitive. Example value: *SAMEi V2lubmVy*
- *SAMEn <base64 encoded text value>*: the row/column must contain at least one cell whose value is NOT equal to the text value for the rule to apply. You can also search part of the row/column using the optional column/row specifier that is described later on. Example value: *SAMEn V2lubmVy*
- *SAMEni <base64 encoded text value>*: same as above but case insensitive. Example value: *SAMEni V2lubmVy*
- *CONTAIN <base64 encoded text value>*: the row/column must contain at least one cell whose value contains the text value for the rule to apply. You can also search part of the row/column using the optional column/row specifier that is described later on. Example value: *CONTAIN V2lubmVy*
- *CONTAINi <base64 encoded text value>*: same as above but case insensitive. Example value: *CONTAINi V2lubmVy*
- *CONTAINn <base64 encoded text value>*: the row/column must contain at least one cell whose value does not contain the text value for the rule to apply. You can also search part of the row/column using the optional column/row specifier that is described later on. Example value: *CONTAINn V2lubmVy*
- *CONTAINni <base64 encoded text value>*: same as above but case insensitive. Example value: *CONTAINni V2lubmVy*
- *GREATER <base64 encoded argument>*: the row/column must contain at least one cell whose value is greater than the specified argument for the rule to apply. The argument can be:

1. a numeric value, e.g. #32 → *GREATER IzMy*
2. a date string, e.g. [2013-12-01] or [-30 days] → *GREATER WzIwMTMtMTItMDFd* or *GREATER Wy0zMCBkYXlZXQ==*
3. a text value, e.g. “Jones” → *GREATER 4oCcSm9uZXpJ0=*

Note that the # indicates a numeric value, the double quotes a text value and the square brackets a date string. *IzMy* is the based64 encoded value of #32, *WzIwMTMtMTItMDFd* is the based64 encoded value of [2013-12-01] and *4oCcSm9uZXpJ0=* is the based64 encoded value of “Jones”. The comparison is done according to the specified data type. You can also search part of the row/column using the optional column/row specifier that is described later on.

- *GREATERE <base64 encoded argument>*: the row/column must contain at least one cell whose value is greater than or equal to the specified argument for the rule to

apply. See *GREATER* above for examples and available argument data types.

- *LESS* <base64 encoded argument>: the row/column must contain at least one cell whose value is less than the specified argument for the rule to apply. You can also search part of the row/column using the optional column/row specifier that is described later on. See *GREATER* above for examples and available argument data types.
- *LESSE* <base64 encoded argument>: the row/column must contain at least one cell whose value is less than or equal to the specified argument for the rule to apply. See *GREATER* above for examples and available argument data types.
- *EQUAL* <base64 encoded argument>: the row/column must contain at least one cell whose value is equal to the specified argument for the rule to apply. You can also search part of the row/column using the optional column/row specifier that is described later on. See *GREATER* above for examples and available argument data types.

One really cool option that you can use is the **column/row specifier** so only in certain columns/rows the comparison will take place. Here is an example:

Suppose that you want to highlight all table rows in which the 4th column contains dates that are recent. The 5th column also contains dates, but they have a different purpose and you don't want to include them in the date comparison. In such case, you can define a range similar to:

GREATER Wy0zMCBkYXlzXQ== [4].

Only cells on the 4th column will be compared with the date argument. You could also specify more columns, using the comma separator as shown in the following range:

GREATER Wy0zMCBkYXlzXQ== [4,6,8]

In this case, cells on 4th, 6th and 8th column will be compared with the date argument.

The optional column/row specifier can be an integer or a list of integers separated by comma and enclosed in square brackets, just like the examples above.

The optional column/row specifier can be used with:

SAMEi, SAMEn, SAMEni, CONTAIN, CONTAINi, CONTAINn, CONTAINni, GREATER, GREATERE, LESS, LESSE, EQUAL

- *MIN* [ROW SEARCH RANGE],[COLUMN SEARCH RANGE]: the row/column cells contain the lowest (minimum) value within the range specified by the row/column range arguments. See below for acceptable values for ROW/COLUMN SEARCH RANGE. Example value: MIN [1-3][1-L1]
- *MAX* [ROW SEARCH RANGE],[COLUMN SEARCH RANGE]: the row/column cells must contain the highest (maximum) value within the range specified by the row/column range arguments. Example value: MAX [1-3][1-L1]
- *MEDIAN* [ROW SEARCH RANGE],[COLUMN SEARCH RANGE]: the row/column cells must contain the middle (median) value within the range specified by the row/column range arguments. Example value: MEDIAN [1-3][1-L1]

If the type is **CELL**, this can be:

- <integer value>,<integer value>: The specific coordinates of a cell in which the rule applies. Example value: 1,3 (i.e. the cell of the intersection of first row, third column)
- <integer or decimal value from>-<integer or decimal value to>: The value range in which a numeric cell value must fall for the rule to apply. For decimal numbers, use

the dot (.) as the separator for the decimal point. Example value: 0-3.5

- *>* *<integer or decimal value from>*: The value range in which a numeric cell value must fall for the rule to apply. For decimal numbers, use the dot (.) as the separator for the decimal point. Example value: *> 3*
- *>=* *<integer or decimal value from>*: Same as above, but instead of "greater than" we use for comparison "greater than or equal". Example value: *>= 3*
- *<* *<integer or decimal value to>*: The value range in which a numeric cell value must fall for the rule to apply. For decimal numbers, use the dot (.) as the separator for the decimal point. Example value: *< 3*
- *<=* *<integer or decimal value to>*: Same as above, but instead of "less than" we use for comparison "less than or equal". Example value: *<= 3*
- *=* *<integer or decimal value to>*: The numeric value that must be equal for the rule to apply. Example value: *= 3*
- *SAME* *<base64 encoded text value>*: the cell must be equal to the text value for the rule to apply. Example value: *SAME V2lubmVy*
- *SAMEi* *<base64 encoded text value>*: same as above but case insensitive. Example value: *SAMEi V2lubmVy*
- *SAMEn* *<base64 encoded text value>*: the cell must NOT be equal to the text value for the rule to apply. Example value: *SAMEn V2lubmVy*
- *SAMEni* *<base64 encoded text value>*: same as above but case insensitive. Example value: *SAMEni V2lubmVy*
- *CONTAIN* *<base64 encoded text value>*: the cell must contain the text value for the rule to apply. Example value: *CONTAIN V2lubmVy*
- *CONTAINi* *<base64 encoded text value>*: same as above but case insensitive. Example value: *CONTAINi V2lubmVy*
- *CONTAINn* *<base64 encoded text value>*: the cell must NOT contain the text value for the rule to apply. Example value: *CONTAINn V2lubmVy*
- *CONTAINni* *<base64 encoded text value>*: same as above but case insensitive. Example value: *CONTAINni V2lubmVy*
- *GREATER* *<base64 encoded argument>*: the row/column must contain at least one cell whose value is greater than the specified argument for the rule to apply. The argument can be:
 1. a numeric value, e.g. #32 → *GREATER IzMy*
 2. a date string, e.g. [2013-12-01] or [-30 days] → *GREATER WzIwMTMtMTItMDFd* or *GREATER Wy0zMCBkYXlXQ==*
 3. a text value, e.g. "Jones" → *GREATER 4oCcSm9uZXPigJ0=*

Note that the # indicates a numeric value, the double quotes a text value and the square brackets a date string. *IzMy* is the based64 encoded value of #32, *WzIwMTMtMTItMDFd* is the based64 encoded value of [2013-12-01] and *4oCcSm9uZXPigJ0=* is the based64 encoded value of "Jones". The comparison is done according to the specified data type.

- *GREATERE* *<base64 encoded argument>*: the row/column must contain at least one cell whose value is greater than or equal to the specified argument for the rule to apply. See GREATER above for examples and available argument data types.
- *LESS* *<base64 encoded argument>*: the row/column must contain at least one cell whose value is less than the specified argument for the rule to apply. See GREATER

above for examples and available argument data types.

- *LESSE* <base64 encoded argument>: the row/column must contain at least one cell whose value is less than or equal to the specified argument for the rule to apply. See GREATER above for examples and available argument data types.
- *EQUAL* <base64 encoded argument>: the row/column must contain at least one cell whose value is equal to the specified argument for the rule to apply. See GREATER above for examples and available argument data types.
- *MIN* [ROW SEARCH RANGE],[COLUMN SEARCH RANGE]: the cell must be numeric and contain the lowest (minimum) value within the range specified by the row/column range arguments. See below for acceptable values for ROW/COLUMN SEARCH RANGE. Example value: *MIN* [1-3][1-L1]
- *MAX* [ROW SEARCH RANGE],[COLUMN SEARCH RANGE]: the cell must be numeric and contain the highest (maximum) value within the range specified by the row/column range arguments. Example value: *MAX* [1-3][1-L1]
- *MEDIAN* [ROW SEARCH RANGE],[COLUMN SEARCH RANGE]: the cell must be numeric and contain the middle (median) value within the range specified by the row/column range arguments. Example value: *MEDIAN* [1-3][1-L1]

If the type element is **TABLE**, this case be:

- *ALL*: the rules applies all times, regardless of the size and the contents of the table
- *ROWS*> <integer value>: The minimum number of rows the table must have for the rule to apply. Example value: *ROWS* > 3
- *ROWS*>= <integer value>: Same as above, but instead of "greater than" we use for comparison "greater than or equal". Example value: *ROWS* >= 3.
- *ROWS*< <integer value>: The maximum number of rows the table must have for the rule to apply. Example value: *ROWS* < 10
- *ROWS*<= <integer value>: Same as above, but instead of "less than" we use for comparison "less than or equal". Example value: *ROWS* <= 10.
- *COLUMNS*> <integer value>: The minimum number of columns the table must have for the rule to apply. Example value: *COLUMNS* > 3
- *COLUMNS*>= <integer value>: Same as above, but instead of "greater than" we use for comparison "greater than or equal". Example value: *COLUMNS* >= 3.
- *COLUMNS*< <integer value>: The maximum number of columns the table must have for the rule to apply. Example value: *COLUMNS* < 10
- *COLUMNS*<= <integer value>: Same as above, but instead of "less than" we use for comparison "less than or equal". Example value: *COLUMNS* <= 10.
- *CELLS*> <integer value>: The minimum number of cells the table must have for the rule to apply. Example value: *CELLS* > 3
- *CELLS*>= <integer value>: Same as above, but instead of "greater than" we use for comparison "greater than or equal". Example value: *CELLS* >= 3.
- *CELLS*< <integer value>: The maximum number of cells the table must have for the rule to apply. Example value: *CELLS* < 10

- *CELLS* <=*integer value*>: Same as above, but instead of "less than" we use for comparison "less than or equal". Example value: *CELLS* <= 10.
- *SAME* <base64 encoded text value>: the row/column cells must be equal to the text value for the rule to apply. Example value: *SAME V2lubmVy*
- *SAMEi* <base64 encoded text value>: same as above but case insensitive. Example value: *SAMEi V2lubmVy*
- *SAMEn* <base64 encoded text value>: the row/column cells must NOT be equal to the text value for the rule to apply. Example value: *SAMEn V2lubmVy*
- *SAMEni* <base64 encoded text value>: same as above but case insensitive. Example value: *SAMEni V2lubmVy*
- *CONTAIN* <base64 encoded text value>: the row/column cells must contain the text value for the rule to apply. Example value: *CONTAIN V2lubmVy*
- *CONTAINi* <base64 encoded text value>: same as above but case insensitive. Example value: *CONTAINi V2lubmVy*
- *CONTAINn* <base64 encoded text value>: the row/column cells must NOT contain the text value for the rule to apply. Example value: *CONTAINn V2lubmVy*
- *CONTAINni* <base64 encoded text value>: same as above but case insensitive. Example value: *CONTAINni V2lubmVy*

The **LIMIT SUBRANGE** can be:

- <integer value from>-<integer value to>: A range of integers which indicates the range of rows or columns you are referring to. Example value: 1-3
- > <integer value from>: A lower limit which indicates the range of rows or columns you are referring to. Example value: > 3
- >= <integer value from>: Same as above, but instead of "greater than" we use for comparison "greater than or equal". Example value: >= 3
- < <integer value to>: An upper limit which indicates the range of rows or columns you are referring to. Example value: < 3
- <= <integer value to>: Same as above, but instead of "less than" we use for comparison "less than or equal". Example value: <= 3
- *FIRST* <integer value>: the integer value indicates the first X rows/columns you are referring to. Example value: *FIRST* 3
- *LAST* <integer value>: the integer value indicates the last X rows/columns you are referring to. Example value: *LAST* 3
- *ALL*: all rows/columns. This is equivalent to range 1-L1. Example value: *ALL*

The **ROW/COLUMN SEARCH RANGE** can be:

- <integer value>: An integer value which indicates which row or column you are referring to. Example value: 1
- <integer value from>-<integer value to>: A range of integers which indicates the range of rows or columns you are referring to. Example value: 1-3
- <integer value>,<integer value>,...,<integer value>: A comma separated list of integers, indicating the specific rows/columns you are referring to. Example value: 1,3,5
- > <integer value from>: A lower limit which indicates the range of rows or columns you are referring to. Example value: > 3
- >= <integer value from>: Same as above, but instead of "greater than" we use for comparison "greater than or equal". Example value: >= 3

- *< <integer value to>*: An upper limit which indicates the range of rows or columns you are referring to. Example value: *< 3*
- *<= <integer value to>*: Same as above, but instead of "less than" we use for comparison "less than or equal". Example value: *<= 3*
- *FIRST <integer value>*: the integer value indicates the first X rows/columns you are referring to. Example value: *FIRST 3*
- *LAST <integer value>*: the integer value indicates the last X rows/columns you are referring to. Example value: *LAST 3*
- *SAME*: the same row/column. This value is considered dynamic, as it changes depending on the current cell we are examining. Example value: *SAME*
- *P<integer value>*: The X previous row/column from the current element. So, for instance if the current id is 5, P1 = 4, P2=3, P3=2, etc. Example value: *P1*
- *N<integer value>*: The X next row/column from the current element. So, for instance if the current id is 5, N1 = 6, N2=7, N3=8, etc. Example value: *N1*
- *ALL*: all rows/columns. This is equivalent to range 1-L1. Example value: *ALL*

Important note: Starting from version 4.0 all text values used in text comparison range selections (CONTAIN, SAME, etc) are stored as base64 encoded string in the rules archive file. For this reason, at the end of the rule form there is a base64 encoder/decoder. Use this utility to convert plain text to base64 encoded text or vice versa.

3. **Range Key:** This field can be used to fine tune the range selection when autospan (i.e. cell merging) occurs. For instance, we may have a table where the second column contains the days of week and the third column contains the activities for that day. In order to make the table easier to read, you apply a rule with Range=ODD and Range Key=2. What this means is that the range counter will increment every time a new day appears on the second column and not on every new table row. Note: In previous versions it was called *Range Count*.
4. **Priority:** This affects the execution order of the rule that in some cases makes a difference. Up to version 5.0, the execution order was defined automatically using an algorithm that was suitable for most users. Nevertheless, in some cases it's hard to decide which rule to execute first as both execution paths make sense. In such cases, use the priority field to specify explicitly the execution order. Note that priority must be an integer number and the higher the priority the faster the rule will be executed. Leave the default priority = 0 for all the rules that you want the system to define their execution order.
5. **Style/CSS Selector:** The CSS selector that will be applied to the specified table element (row/column/cell/table) when the element range is within limits. The specific attributes of the CSS selector need to be defined elsewhere, in a separate CSS file. Example value: *rsheader*
6. **Autospan:** The autospan field indicates whether or not an automatic cell merging should take place when empty neighboring cells are present. The typical case scenario is when the first row of a table is used to display the table title/caption and you want to merge all cells of the first row into a single one.

Note: Autospan should not be used together with some other rules that do not like cell merging. One of them is the dynamic table sorting on the client side which requires a fixed number of cells on each row.

7. **Remove:** Check this box if you want all the table rows/columns that fall in the specified range to be removed. Very handy in cases you want to remove table rows that contain a

specific text value, or dates outside a certain range.

8. **Data/Format:** If you want the cells of the specified range to have a specific format, you can use this field to specify one. For each available datatype there is a list of applicable options, as described in the list below:

- Text:
 - Uppercase: HELLO WORLD
 - Lowercase: hello world
 - Capitalize first letter: Hello world
 - Capitalize first letter of each word: Hello World
- Number:
 - Decimals: most likely 2. Example 12.30
 - Decimal point: For US is the dot, for most European countries is the comma. Example 12,30 (US) 12.30 (Europe)
 - Thousands separator: For US is the comma, for most European countries is the dot. Example:1,000 (US) 1.000 (Europe)
- Currency:
 - Decimals: most likely 2. Example 12.30
 - Decimal point: For US is the dot, for most European countries is the comma. Example 12,30 (US) 12.30 (Europe)
 - Thousands separator: For US is the comma, for most European countries is the dot. Example:1,000 (US) 1.000 (Europe)
 - Currency symbol: The currency symbol such as € or \$. Note, the currency symbol is not required and it can be omitted.
 - Currency symbol position: If the currency symbol is present, whether it should appear before or after the numeric value.
- Date:
 - DD-MM-YY (e.g. 21-10-09)
 - DD/MM/YY (e.g. 21/10/09)
 - DD.MM.YY (e.g. 21.10.09)
 - MM-DD-YY (e.g. 10-21-09)
 - MM/DD/YY (e.g. 10/21/09)
 - DD-MM-YYYY (e.g. 21-10-2009)
 - DD.MM.YYYY (e.g. 21.10.2009)
 - DD/Month/YYYY (e.g. 21/Oct/2009)
 - MM-DD-YYYY (e.g. 10-21-2009)
 - MM/DD/YYYY (e.g. 10/21/2009)
 - Month Day, Year (e.g. Jan 1, 2009)
 - Weekday, DD-Month-YYYY (e.g. Monday, 21-Oct-2009)

- Weekday, DD/Month/Year (e.g. Monday, 21/Oct/2009)
- Weekday, Month Day, Year (e.g. Monday, Oct 1, 2009)
- Weekday, DD-Month-YYYY (e.g. Monday, 21-Oct-2009)
- Weekday, Day Month (e.g. Monday, 21 October)
- Weekday, Month Day (e.g. Monday, October 21)

9. **Data/Replacement:** Another new feature that may come in handy is the ability to replace one text with another. For example you could replace the text *TS* with *Total Sales* or the word *STAR* with the html code ``. Note, the flag CS stands for “Case Sensitive”. Starting from version 4.0 the text values need to be base64 encoded. You can use the base64 encoder/decoder at the end of the Rule form to convert between plain text and base64 encoded text.

10. **Data/Calculation:** With Tabulizer you can do simple calculations based on the values of other cells, similar to Word or Excel. For instance, you can calculate the sum of all the cells above, or find the average value of all cells on the right. The calculation applies to numeric values only; cells with non numeric values get ignored. You can use one of the system calculation functions listed below, or define your own custom function:

- *Add*
- *Multiply*
- *Average*
- *Median*
- *Min*
- *Max*

Let's say you want to add all the (numeric values) above. Here are the correct settings:

Function: *ADD*

Arguments Range: *[SAME][1-P1]*

Custom Arg:

The function name is *ADD*, since you are going to use the pre-built function *ADD*, that adds all specified table cells. These are defined in the arguments range in the following format: *[row range][column range]*

In our example:

- **row range:** *SAME* → same row with the current cell
- **column range:** *1-P1* → P1 means the previous element from the current one, therefore 1-P1 means all columns from 1 up to the previous column, compared to the column of the current cell.

If the current cell (on which the calculation is executed) is the intersection of row #3 and column #5, then for cell[3,5] the specified range *[SAME][1-P1]* = *range[3][1-4]* => *cell[3,1] + cell[3,2] + cell[3,3] + cell[3,4]*.

For a better understanding of what values the Arguments Range can take, please read the paragraph on “ROW/COLUMN SEARCH RANGE”.

Another advanced feature when it comes to calculation is that you can build your own **custom calculation functions** and distribute them along with rest of the ruleset archive. This advanced feature will be covered elsewhere.

9. **Table/Split:** When you have a large table, it may be a good idea to split it into smaller tables. These tables can be on the same page, or on multiple pages. Here are the available options:
 - *Max Rows/Table:* The number of rows each smaller table will have, taking into account any column span that may occur.
 - *Group Rows By Value of Column #:* All rows that have the same value in the selected column will be grouped together to the same table.
 - *Multipart:* this means that the table will break into smaller tables on the same page.
 - *Multipage:* this means that the table will break into smaller tables on separate pages.
 - *Index:* When you add the keyword index, an index of all multipart tables will be created.
 - *Top:* the top rows of the original table that will be used as top header to all smaller tables.
 - *Bottom:* the bottom rows of the original table that will be used as bottom header to all smaller tables.

10. **Table/Pagination:** Another approach to display a large table into a smaller space is to use in-line pagination. The pagination takes places on the client-side via Javascript code. Here are the available parameters for this feature:
 - *Type:* Select if you want to display only the “next/previous page” arrows, or the arrows and the page numbers.
 - *Limit (Rows/Page):* How many rows to display on each page table. The default value is 10 table rows per page.
 - *Limit Selection:* Where to place the limit selection control.
 - *Position:* Where the pagination control will appear (e.g. top-right side of the table)

11. **Table/Scrollbars:** If the table contents are too wide or too long, you can add horizontal and/or vertical scrollbars. Not in the case of vertical scrollbars, the top header row will remain fixed and it will not get scrolled down with the rest of the table contents. In order to activate this feature simple type the scrollbar dimensions.

Table/Scrollbars [?]:	Horizontal Scroll:	500px Sam
	Vertical Scroll:	Sam

12. **Table/Sort:** Tabulizer allows you to sort your table data on the client-side by activating this feature. You can set the sort order (ascending/descending) and the initial sorting header, i.e. if “Sort by Column #” is 2 it means that the table will initially be sorted by the header of the second column. Once the table is displayed, the user can click on other columns headers and change the sorting order.

Important note: Table sorting does not like rowspans and columns spans because cell merging makes the dynamic sorting complicated. For this reason, if you have in the same ruleset another rule that uses autospan you will need to remove it.

13. **Table/Search Filter:** When a table has many rows it might be difficult to spot what you are looking for. The Search Filter comes to rescue and you can type a text and only the rows that contain this particular text will remain on display. Starting with version 5.0 you have many more options when it comes to search filtering, that are described below.

- **Table Filter:** Table filters will be applied to the whole table, not any specific column. The parameters you can set are:
 1. Enabled: Check this to enable table-wide search filtering
 2. Header Size: How many top headers rows are regarded as “header”. The header is excluded from any search filtering, so you may increase the default value of 1.
 3. Position: Where to display the search filter box. This box, like any other element, can be styled with regular CSS statements.

You can also pre-populate the value of the search filter using the URL parameter *filter_preselection* that has the following format:

`table_id_1:value_1^table_id_2:value_2^...^table_id_n:value_n`

Note that:

- `table_id` is not the id of the table HTML element, but the table ordering (the sequence of appearance in the page, counting only tables with search filtering enabled) that starts from 0, instead of 1. So, the first table in the page has `table_id = 0`, the second has `table_id = 1` and so on.
 - `value` should be URL encoded, as this is part of the URL.
- **Column Filters:** Sometimes you want to filter specific columns, not just the whole table. One of the great new features that came along with Tabulizer version 5.0 is the full control you have over the column search filters. In the previous versions, when you type the key phrase in the filter input box all column cells would be searched if they contained the phrase.

For instance, if the search phrase was "ten" and all cells that contained anywhere the string "ten" would be included in the results, e.g. Ten, Tenterous, Apten etc. This is called a smart search and it's still available as the default search method. On top of that, there are a few other search methods that may be suitable in some cases and they are described in the table below:

Search Method	Description
smart	The default search method. Will return all cells that contain anywhere the key

	phrase.
exact	This method will return only cells that contain the exact phrase. Example: The key phrase is "20" will return only cells with value "20", but not "120" or "220", i.e. that contain the value "20".
start_with	This method will return only cells that contain the key phrase at the beginning. Example: The key phrase "20" will return "20" and "209" but not "320".
numeric_period	Use this method to search for numeric ranges. For instance, if the column contain prices and you want to display only cells whose price is greater than \$1000 or less than \$500. You could also search for prices between \$500 and \$1000. The syntax is quite simple and it's summarized in the examples below: 1000 : will search for all values equal to 1000 > 1000 : will search for all values greater then 1000 < 500 : will search for all values less then 1000 500 & 1000 : will search for all values between 500 and 1000 This search method is smart enough to remove currency symbol, or other extra characters. Nevertheless, when you have decimal numbers (e.g. 12.564) the period will be treated as the separator for the decimal number, and the comma (,) as the thousands separator. If it's the other way around use the next search method numeric_comma.
numeric_comma	Same as above. The only difference is in decimal numbers, where the comma will be treated as the separator for the decimal number, and the period (.) as the thousands separator.

Apart from the search method, you can also specify the control type for our column filters. This can be:

1. input: An input search box, where you can type your key phrase. This is the default control type.
2. select: An select drop-down box, where you can select a value from a populated list with all the unique cell values for the specified column. This is recommended when the column contains a limited number of unique cell values.

The column id, the search method and the control type are combined using the following format:

column_id_1:control_type_1:search_method_1,column_id_2:control_type_2:search_method_2,...,column_id_n:control_type_n:search_method_n

Only the column_id is required. The control type and the search method will take the default value, if omitted. So, for instance:

Initial	Equivalent
1,2,3	1:input:smart,2:input:smart,3:input:smart
1,2:select,3:input	1:input:smart,2:select:smart,3:input:smart
1:input:start_with,2:select:exact,3:input	1:input:start_with,2:select:exact,3:input:smart

The column search filters appear in the table header, but you can specify:

- The exact header row that they will appear. The default value is 1, which means they will appear on the top row, but you can change that if you want to keep the top row for the headers and set the filter's row to be the second one (header row = 2).
- Also, you can set the header size to be any value. This is useful, if you want to exclude some header rows from the filtering process.

Pre-selected filter values

It is possible to pre-populate the value of an input search filter or pre-select a drop-down control box using the URL parameter *column_filter_preselection*, using the following format:

table_id_1:column_id_1:value_1^table_id_2:column_id_2:value_2^...^table_id_n:column_id_n:value_n

Note that:

- table_id is not the id of the table HTML element, but the table ordering (the sequence of appearance in the page, counting only tables with search filtering enabled) that starts from 0, instead of 1. So, the first table in the page has table_id = 0, the second has table_id = 1 and so on.
- column_id is the column ordering (the sequence of appearance in the row) that starts from 0, instead of 1. So, the first row column has column_id = 0, the second

has `column_id = 1` and so on.

- value should be URL encoded, as this is part of the URL.
14. **Table/Responsive:** The “responsive design” is the next big thing in web design, as small devices (iPads, smart phones, etc) increase their share in web browsing. It's called responsive because the goal is to have a web page (or a table in our case) that “responds” or adjusts to the screen size of the user's device. One thing that needs to be clear in your mind is that “responsiveness” is a characteristic not a concrete implementation and this is way Tabulizer offers you 6 different responsive design patterns to choose from. Not everyone is good for everybody, so you need to examine them to see which one is better for your particular needs. The six responsive patterns were selected and implemented based on their current popularity among internet users and they are:
 - Horizontal Scrollbar
 - Table reflow
 - Header selection
 - Fixed headers + Expand
 - Fixed left header + Scroll
 - Flip headers
 15. **Table/Modify:** Use this feature to define a custom function that will accept as input the table, modify it in some way and return it for further processing by Tabulizer.
 16. **Table/Export:** Exporting table data as file is as simple as checking the enable box.
 - Allow Download: Check if you want the user to be able to download the table
 - Allow Email: Check if you want the user to be able to email the table
 - Strip Tags: Check if you want to remove the HTML tags from the table data before saving them into the table.
 17. **Table/Prepend:** This feature gives you the possibility to add text or HTML code right before the table, all the times or under certain conditions (combined with the proper range value).
- It is possible to use javascript code as well, but note that if your Joomla editor is using filtering (for security purposes) that code will get stripped out. So, you may need to disable input filtering.
18. **Table/Append:** This feature gives you the possibility to add text or HTML code right after the table, all the times or under certain conditions (combined with the proper range value). The note about input filtering stripping out HTML code applies here as well.
 19. **Add Files:** This gives you a chance to add CSS and Javascript files required by your ruleset. For security purposes, these files should reside only in the appropriate folders, which are:
 - {joomla root directory}/template/tabulizer/css ← for CSS files
 - {joomla root directory}/template/tabulizer/js ← for Javascript files

If you want to add more than one files, use the semicolon (;) as your file's separator.
 20. **Table/Graph Conversion:** One new exciting new feature of Tabulizer v4.0 is the ability to convert tables into graphs. In order to do that you need a graph ruleset that specifies exactly

the various aspects of the graph, e.g. its type, colors, preferences, etc. Currently you can create your own graph ruleset online at www.tabulizer.com. The resulting ruleset archive contains the graph ruleset file that is stored in *{your joomla root directory}/templates/tabulizer/graph* folder.

Currently, the online graph creation wizard creates a ruleset archive that is complete, therefore it is not required to create your own ruleset and add a new rule with Table/Graph field set to the graph ruleset file value. So, for the time being just remember that is possible that a graph ruleset created with the online creation wizard can be used into multiple rulesets by creating a new rule and setting the Table/Graph field to the appropriate value.

Example value:

Table/Graph: *rs_ctsjqeex.xml*

The *rs_ctsjqeex.xml* resides in *{your joomla root directory}/templates/tabulizer/graph* folder and it was added there when you imported the *rs_ctsjqeex.zip* archive file that was produced by the online graph creation wizard at www.tabulizer.com

A rule belongs to a ruleset, so before you create a new rule you must create first the corresponding [ruleset](#).

What is a ruleset

A ruleset is a set (i.e. a group) of [rules](#). When you insert a new table via the Tabulizer editor plugin you are asked to specify the applicable ruleset. All rules that belong to the selected ruleset will be applied during the conversion of the input text to the final table HTML code. In other words, a ruleset is nothing more than a group of rules that all together achieve the desired visual appearance and data transformation. When you create a new ruleset, you must specify the following properties/fields:

1. **Ruleset Title:** The title of the ruleset. Because ruleset selection is based on the title field, (a) it must be unique, i.e. each ruleset must have a unique title and no two rulesets should share the same one (b) it must be short but descriptive.
2. **Ruleset Description:** An optional description of the ruleset.
3. **Ruleset Name:** The ruleset name identifies the ruleset in all internal operations and it can be any combination of latin letters (a-z), digits (0-9), the underscore (_) and the hyphen (-). No white spaces or special characters are permitted. The ruleset name, even though it does not appear on the ruleset selection controls, it must be globally unique, i.e. no two rulesets should have the same name.
4. **Ruleset Suffix:** The ruleset suffix is a CSS selector that will be added to the resulting table css class. For example, if the ruleset suffix is "ruleset_nbl" and we apply the ruleset to an input text, the HTML source code of the resulting table might look like this:

```
<table class="tabtable-ruleset_nbl"> ... </table>
```

 The combined CSS selector "tabtable-ruleset_nbl" could be defined in a css file to style the whole table, similar to the example of the [Overview](#) paragraph.
5. **Ruleset Style:** The associated CSS file that is needed by the ruleset. If left empty, the ruleset style will be inherited by the archive style. The usual approach would be to leave this field empty and then define the style in the Ruleset Archive edit form, since most of the times all rulesets that belong to the same archive share the same CSS file.
6. **Sample data:** If you check this optional field, a textarea appears where you can store your sample data for the preview operation. If you leave this field blank, when one previews the

ruleset, random data will be used instead.

In order to create a ruleset, you must create first a [ruleset archive](#) that will contain it.

What is a ruleset archive

A ruleset archive is an XML file that contains one or more [rulesets](#). Even though it is possible to edit a ruleset archive via an XML editor or a simple text editor, like Windows Notepad, it is recommended that you create, edit and delete a ruleset archive via the Tabulizer component. When you create a new ruleset archive, you must specify the following properties/fields:

1. **Archive Filename:** The filename of the archive. It should have an xml extension and like every other file on the system it must be unique, i.e. no two ruleset archives can have the same filename. Important! The xml extension should be in lowercase (e.g. archive.xml, not archive.XML) otherwise the Tabulizer might not recognize it.
2. **Archive Title:** The title of the ruleset archive can be any short description of the archive.
3. **Archive Name:** The name of the ruleset archive is used internally and it should be globally unique, i.e. no two ruleset archives should have the same name.
4. **Archive Style:** The associated CSS file that is needed by the ruleset. This value will be inherited by all containing rulesets.
5. **Archive Version:** The version of this ruleset archive. Useful if you have multiple versions of the same archive.
6. **Author Name:** The author of this archive (full name).
7. **Author Email:** The author's email address.
8. **Author URL:** The author's web address (URL).

The default directory in which all ruleset archives reside is *templates/tabulizer/rules*.

Preview ruleset styling

The Tabulizer component allows you to preview the ruleset, so you can have an idea of how it looks like before you use it. This is very useful for rulesets that were created by someone else, or for a new ruleset you are creating and you want to verify that it looks as expected.

In order to preview a ruleset, from the Tabulizer component click on ruleset archive that contains the ruleset you want to preview and then click on the "Preview" link in the actions column. In this case you will preview all rulesets of the particular archive. If you want to preview a single ruleset, the click first on the "View" link of the ruleset archive and then click on the "Preview" link of the desired ruleset.

When previewing a ruleset and no sample data are specified, Tabulizer will create a random sample data set for you. Most of the times this is sufficient, but if the ruleset has specific requirements (let's say a replacement rule and needs to be demonstrated) you need to set the sample data of the ruleset manually.

Automatically create and edit CSS skeleton for rulesets

Since for each styling rule you define, there must be a corresponding CSS selector in the companion CSS file, the Tabulizer component offers you the option to create automatically a skeleton code for all CSS selectors defined in the ruleset with a single click. For instance, if you export the following ruleset archive (basic_rulesets.xml):

```
<?xml version="1.0" encoding="utf-8"?>
<rules name="basic_rulesets" title="Basic Rulesets" style="basic_rulesets.css">
<ruleset name="ruleset_nbl" title="National Basketball League" suffix="ruleset_nbl" >
<rule element="row" range="1" style="nbl_header"></rule>
<rule element="column" range="1" style="nbl_teams"></rule>
<rule element="row" range="EVEN" style="row_even"></rule>
</ruleset>
</rules>
```

it will produce the following CSS skeleton:

```
/* ruleset_nbl */
table.tabtable-ruleset_nbl {}
table.tabtable-ruleset_nbl tr.tabrow {}
table.tabtable-ruleset_nbl tr.tabrow td.tabcol {}
table.tabtable-ruleset_nbl tr.tabrow td.nbl_teams {}
table.tabtable-ruleset_nbl tr.nbl_header {}
table.tabtable-ruleset_nbl tr.nbl_header td.tabcol {}
table.tabtable-ruleset_nbl tr.nbl_header td.nbl_teams {}
table.tabtable-ruleset_nbl tr.row_even {}
table.tabtable-ruleset_nbl tr.row_even td.tabcol {}
table.tabtable-ruleset_nbl tr.row_even td.nbl_teams {}
```

Not all CSS selectors need to be defined. If don't need a selector you can either keep it for future use or delete it in order to make the resulting CSS file smaller and cleaner. Note also that the CSS skeleton contains no styling properties (background color , font size, etc) for the exported CSS selectors. This is a task for you to do, based on your specific needs.


Ruleset Archives

 New Archive
  Import Archive
  Delete Archive
  Data Sources

Click here to create/edit the CSS file

☐	Archive Title	Archive Name	Archive Filename	Archive Style
☐	Basic Rulesets	basic_rulesets	basic_rulesets.xml	basic_rulesets.css [Edit]

CSS Skeleton: [Append recommended CSS declarations at the end of the CSS file](#)

If you save the CSS file and it's not already created, it will be created for you and stored in the *templates/tabulizer/css* folder. At the end of the CSS editing form you will find the current preview of the ruleset. This is very convenient as you can watch how the appearance changes as you set the CSS selectors.

When you modify a CSS file and see no changes in the preview section, you may need to reload the page just to make sure the browser does not use the older version of the CSS file.

Where are the files located

All files used by ruleset archives are stored in the appropriate *{your wordpress directory}/wp-content/plugins/tabulizer/templates/tabulizer* subfolder. More specifically, you will find the following subfolders that contain files used by the available rulesets:

- **rules:** the actual rules files (extension xml)
- **css:** the companion CSS files
- **images:** image files
- **js:** javascript files
- **calc:** the built-in and custom (user defined) calculation functions.
- **modify:** the built-in and custom (user defined) modification functions.
- **graph:** graph rulesets (how to draw a dynamic graph – used for converting a table into a graph)
- **docs:** documentation files for the various ruleset archives.
- **data:** the data files used by the data sources (e.g. Excel and CSV).
- **data_sources:** the installation files of the various data sources.
- **language:** the language files used by the modification functions.
- **htc:** behaviour files for internet explorer.

The location of these folders/files cannot be changed.

Example: Creating a ruleset from scratch

In order to demonstrate the concepts described previously, we will give an example of how to create your own ruleset that you will use to style a table for your regional sales. If you are not familiar with the terms “rules”, “rulesets” and “ruleset archives” please read the previous section in this document.

Setting the requirements

The first step is to write down your styling requirements. In this example we assume the requirements are:

- You want the first row to have white bold letters on a blue background
- You want the first column to have bold black letters on a blueish background
- You want even rows to have a slightly greyish background, so it is easier to read the table rows
- You want the last row to have an orange background with bold letters
- You want cells with large values (let's say larger than 50) to have a yellow background, so it is easier to visually spot regions/periods with large sales.

Based on the previous requirements, a sample sales table would look like this:

Region/Period	June	July	August
North	10	5	19
South	15	17	16
East	20	65	24
West	16	28	27
Total	61	115	86

Creating the rules

Each requirement most likely will correspond to one styling rule. In our example, the following rules must be created:

Rule #	Type	Range	Style/CSS Selector
1	Row	1	st_periods
2	Column	1	st_regions
3	Row	EVEN	st_row_even
4	Row	L1	st_total
5	Cell	> 50	st_large_amount

We group all these five rules in a ruleset with the following properties:

Rulset Title	Regional Sales
Ruleset Description	The regional sales of our company
Ruleset Name	regional_sales
Ruleset Suffix	regional_sales
Ruleset Style	
Sample Data	No

Finally, we create a new ruleset archive file to store the ruleset with the following properties:

Archive Filename	sales.xml
Archive Title	Sales Rulesets
Archive Name	sales
Archive Style	sales.css

Of course, the actual order of ruleset creation is the opposite, i.e. we first create the ruleset archive, then the ruleset and finally the rules. We present them in the opposite order, because it's closer to the way we conceptually design the rules in our mind.

Defining the CSS Selectors.

So far, we have created the rulesets but we have not specify how they will be interpreted. For instance, we have said the we want to apply the styling selector *st_periods* to the first row of the table, but we have not specified the properties of this selector (in our example: white bold letters on a blue background). The definition of all CSS selectors is done in separate CSS files, unless of course this is done already. Let's define them right now:

```
/* first row */
tr.st_periods { color: #FFFFFF; background-color: #0084D1; font-weight: bold; }
/* first column */
td.st_regions { color: #000000; background-color: #83CAFF; font-weight: bold; }
/* even rows */
tr.st_row_even { color: #000000; background-color: #E6E6E6; }
/* last row */
tr.st_total { color: #000000; background-color: #FFD320; font-weight: bold; }
/* cells with large amounts */
td.st_large_amount { color: #000000; background-color: #FFFF99; }
```

```
/* take special care of intersecting cells */
```

```
tr.st_periods td.st_regions { color: #FFFFFF; background-color: #0084D1; font-weight: bold; }
```

```
tr.st_total td.st_large_amount { color: #000000; background-color: #FFD320; font-weight: bold; }
```

```
/* apply some styling to the whole table */
```

```
.tabtable-regional_sales { background-color: #FFFFFF; }
```

```
table.tabtable-regional_sales tr td.tabcol { padding: 5px; }
```

Save this file as **sales.css** in the *templates/tabulizer/css* directory, which is created automatically during the Tabulizer installation. Notice, that we have set the archive style to this value, and as a result, when a Tabulizer creates a table with the selected ruleset a CSS directive will be appended, that looks like this: `{tabulizer:include style[sales.css] id[tab_goustH6r82]}`. This directive instructs the TabulizerCSS plugin to include the sales.css file automatically.

The screenshot displays the Tabulizer web interface. At the top is the 'Ruleset Archives' section with a table listing archives. Below it is the 'Ruleset Archive: Sales Rulesets' section, and at the bottom is the 'Ruleset: Regional Sales' section. Red arrows point to the 'View' links in the 'Actions' column of the tables in the 'Ruleset Archives' and 'Ruleset Archive: Sales Rulesets' sections.

Archive Title	Archive Name	Archive Filename	Archive Style	Actions
Sales Rulesets	sales	sales.xml	sales.css [Edit]	View Preview Edit Delete

Ruleset Title	Ruleset Name	Ruleset Suffix	Ruleset Style	Actions
Regional Sales	regional_sales	regional_sales		View Preview Edit Delete

Element	Range	Range Key	Element Section	Style/CSS Selector	Rule Short Description	Actions
row	1	0		st_periods		Edit Delete
column	1	0		st_regions		Edit Delete
row	EVEN	0		st_row_even		Edit Delete
row	L1	0		st_total		Edit Delete
cell	>50	0		st_large_amount		Edit Delete

Putting it all together

So far we have created the ruleset and we have define the CSS selectors. The last step is to verify that the resulting sales table appears as expected. To do so, we create a new article (Content → Article Manager → Add New Article) and we click on the **Tabulize!** button to pop-up the Tabulizer form. If there is no **Tabulize!** button, make sure you have installed and activated the Tabulizer editor plugin.

In the form that appears, type in the Input Text box the following sample data and click on the **Convert** button, after you have set the Column separator to “Comma (,)” and the Ruleset to “Regional Sales”.

Region/Period,June,July,August

North,10,5,19

South,15,17,16

East,20,65,24

West,16,28,27

Total,61,115,86

Click on the **Insert** button to copy the produced HTML to your article's body. Save the article and preview it (from the site's view, not the admin view). The end result should look like this:

Region/Period	June	July	August
North	10	5	19
South	15	17	16
East	20	65	24
West	16	28	27
Total	61	115	86

Note that it is quite common, that some parts of your table may appear different because some parts of your table are defined differently in your template's CSS files. In order to override these definitions, you must define your CSS selectors with **higher specificity** (search the internet for “css selectors precedence” to understand how CSS selectors are applied). Alternatively, you could use different CSS selectors to avoid the conflict between template's CSS defines and Tabulizer CSS defines.

Naming conventions

In our example we used **regional_sales** as our ruleset name. This is acceptable if we developed the ruleset for local use, but what if we developed this ruleset for a third-party site? Since ruleset names must be unique on any given system, we want to avoid name conflicts by using a proper naming convention. Tabulizer has adopted a naming convention similar to Java, so a ruleset name with global distribution in mind should start with the website of the developer in reverse order. So, for example if **regional_sales** were developed by **alterora.gr**, the proper ruleset name would be **gr.alterora.regional_sales**, the ruleset archive file would be **gr.alterora.sales.xml** and the associated CSS file **gr.alterora.sales.css**.

Taking our example to the next level

So far we have used only styling rules. We can add a few more rules in order to:

- Calculate automatically the total sum of the sales for each month
- Apply the “currency” format in our sales amounts.
- Merge the cells of the top row of the table that will contain the title/caption of our table

Calculating automatically the total sum

In our “Regional Sales” ruleset, we add the following rule:

Rule #	Type	Range	Data/Calculation
6	Row	L1	Function: Add Arguments Range: [1-L2],[same]

What this rule says is that we want the cells of the last row (L1) to be the sum of all the numeric cells above (row range 1-L2, column range: SAME). The last row contains the total sales of each month, so there is no need to calculate it elsewhere. Note, we define range as “L1” instead of “6” because even though that last row is the sixth row and therefore currently the two definitions have the same effect, if we add a new row in the table the range “6” would be no longer accurate.

Format the cells as currency

Since our table cells contain amounts, it makes perfect sense to format them as currency. We can add a currency symbol, to add more clarity, or leave each amount/cell with no currency symbol. In our example, we choose the former option.

Rule #	Type	Range	Data/Format
7	Column	LAST 3	• Format: Currency

			- Decimals: 2 - Decimal point: comma - Thousands separator: Period (.) - Currency symbol: € - Currency symbol position: Before the amount
--	--	--	--

We choose the European currency representation and we use the euro sign as our currency symbol. The range “LAST 3” means that we want to format the cells of the last 3 columns, i.e. the 2nd column (June sales), the 3rd column (July sales) and the 4th column (August sales).

Using Autospin for our table title

For better clarity we could add a new row at the top of the table that will contain a title/caption for our table. Let's say that the caption of our table is “Summer sales”. If we do not apply any cell merging the table will look like this:

Summer Sales			
Region Period	June	July	August
North	10	5	19
South	15	17	16
East	20	65	24
West	16	28	27
Total			

It is much more aesthetically pleasant if we merge the empty cells of the top row, by applying the following autospin rule:

Rule #	Type	Range	Data/Calculation
8	Row	1	Autospin (checked)

The end result would be like this:

Summer Sales			
Region Period	June	July	August
North	10	5	19

South	15	17	16
East	20	65	24
West	16	28	27
Total			

Putting it all together

Let's try the three new rules we have added in our example ruleset. As previously, we create a new article (Content → Article Manager → Add New Article) and we click on the **Tabulize!** button to pop-up the Tabulizer form.

In the form that appears, type in the Input Text box the following sample data and click on the **Convert** button, after you have set the Column separator to “Comma (,)” and the Ruleset to “Regional Sales”.

```
Summer Sales,,,
Region/Period,June,July,August
North,10,5,19
South,15,17,16
East,20,65,24
West,16,28,27
Total,,,
```

Notice, that we left the last row with the totals empty, but we did put the required number of commas to indicate the presence of empty cells. The same applies to the first row, i.e. we added as many commas as the number of empty cells.

Summer Sales			
Region/Period	June	July	August
North	€10.00	€5.00	€19.00
South	€15.00	€17.00	€16.00
East	€20.00	€65.00	€24.00
West	€16.00	€28.00	€27.00
Total	€61.00	€115.00	€86.00

Click on the **Insert** button to copy the produced HTML to your article's body. Save the article and preview it (from the site's view, not the admin view). The end result should look like this:

For your reference, final version of the ruleset archive (sales.xml) and the corresponding CSS file (sales.css) is given below:

sales.xml

```
<?xml version="1.0" encoding="utf-8"?>
<rules name="sales" title="Sales Rulesets" style="sales.css">
<meta version="1" compatibility="4" generator="Tabulizer v.4.0.0" author_name="Super User"
author_email="info@alterora.gr"/>
<ruleset name="regional_sales" title="Regional Sales" description="The regional sales of our
company" suffix="regional_sales" >
  <rule element="row" range="1" style="st_periods" ></rule>
  <rule element="column" range="1" style="st_regions" ></rule>
  <rule element="row" range="EVEN" style="st_row_even" ></rule>
  <rule element="row" range="L1" style="st_total" ></rule>
  <rule element="cell" range="&gt;50" style="st_large_amount" ></rule>
  <rule element="row" range="L1" calculation="add$[1-L2],[same]$" ></rule>
  <rule element="column" range="LAST 3" format="400^2*2*2* €*1" ></rule>
  <rule element="row" range="1" autospan="1" ></rule>
</ruleset>
</rules>
```

sales.css

```
/* first row */
tr.st_periods { color: #FFFFFF; background-color: #0084D1; font-weight: bold; }
/* first column */
td.st_regions { color: #000000; background-color: #83CAFF; font-weight: bold; }
/* even rows */
tr.st_row_even { color: #000000; background-color: #E6E6E6; }
/* last row */
tr.st_total { color: #000000; background-color: #FFD320; font-weight: bold; }
/* cells with large amounts */
td.st_large_amount { color: #000000; background-color: #FFFF99; }
/* take special care of intersecting cells */
tr.st_periods td.st_regions { color: #FFFFFF; background-color: #0084D1; font-weight: bold; }
tr.st_total td.st_large_amount { color: #000000; background-color: #FFD320; font-weight: bold; }
/* apply some styling to the whole table */
.tabtable-regional_sales { background-color: #FFFFFF; }
table.tabtable-regional_sales tr td.tabcol { padding: 5px; }
```

Importing ruleset archives


Not everybody is a web developer or a graphic designer. For this reason, it is perfectly normal for most people not to have a full understanding of what an XML file is or what CSS stands for. If you are not a technically oriented person or you feel you don't have enough time to go through the learning curve of mastering the inner workings of ruleset creation, help is at hand.

You can choose one of the followings:


1. Use the online creation wizard available at www.tabulizer.com. This is very easy to use and it's ideal for simple tables.
2. Download a ruleset archive from the online catalog, also available at www.tabulizer.com. There is a preview button to see how a ruleset looks like before downloading it.
3. Ask us to create a custom-made ruleset specifically for your needs.

Once you have created or downloaded the desired ruleset archive you need to import it into your system. To do so, click on the **Import Archive** button and select the zipped archive that you have stored in your local disk. Click the **Import** button and the ruleset(s) is ready to use.

Step 1: Click on the Import Archive button



Step 2: Click on the Import button



Request a custom-made ruleset for you.

For a small fee, you can ask us to create a ruleset specifically for you. You can describe to us what you need, using one of the following ways:

- 1) Use a sample table you have created in Word. In your request, append the sample Word document.

- 2) Use a sample table you have found in a web page. In your request, send us the URL (address) of the web page that contains the table and some instructions on how to identify the table (if there more than one tables in that page).
- 3) Use a short but accurate description of how the resulting table should look like.

Example:

- First row must have orange background and white bold letters.
- Last row should have light green background and red letters (normal weight).
- etc

Once we have your requirements, we will send you a reply with the cost. If you agree to the price, we will create and send you the ruleset as a zipped archive that you can import as described in a previous paragraph.

Copying tables from another application

All major text processing/spreadsheet application have the ability to export their data into various formats. Therefore, similar procedures to those described in the following paragraphs exists for many other applications (including the OpenOffice suite).

Importing tables directly from an Excel document

Starting from version 3.0 Tabulizer can import data directly from an Excel file, without the need to export data in CSV format. Tabulizer 4.0 support all common Excel file types, that is:

- Excel 2007 (SpreadsheetML)
- BIFF5 (Excel 5.0 / Excel 95)
- BIFF8 (Excel 97 and later)


When you import data from Excel you need to take into consideration the following constraints:

- 1) The file should have the *.xls or *.xlsx extension (as mentioned previously)
- 2) The file size should not be very large. You will get an error message if the file size is too long (larger than 8MB to be precise, but you can lift this limit).
- 3) You need to have special user rights in order to execute this operation. The reason is that for security purposes, not everybody should be able to upload files to the server. When you are importing data from an excel file, what you are doing essentially is you uploading a file to the web server. Initially only administrators/super administrators can use this feature, but you can add as many user groups as you wish by changing the related permission parameter.


When you are importing directly from Excel you have the following options:

- 1) **Read hyperlinks:** If excel cells have hyperlinks they will be preserved during importation.
- 2) **Read Images:** If the excel cells contain images, they will be imported, saved to the {joomla root}/images/tabulizer folder and added automatically to the produced HTML table.
- 3) **Keep font style:** Check this option if you want to preserve the bold, italic or strike-through font styles during importation. You can specify what will be preserved by editing the **Excel Reading Preferences** section of the User Preferences page.
- 4) **Keep color:** The font color and/or the background color is preserved when this option is checked. You can specify what will be preserved by editing the **Excel Reading Preferences** section of the User Preferences page.
- 5) **Remove empty row/columns:** When you select the importation area you may select a larger one than the actual area that contains the data for your convenience. When this option is checked, empty rows and columns outside the data area will be removed automatically.

When you are importing an Excel file you need to specify apart from the filename, the importation area. To do so you need to specify the upper-left and the bottom-right cells of the selected area using the Excel coordinates of these two cells. Below is an example where the **Sheet Selection** should be set to **D6:F8**



The **Sheet Name** is the exact label of the selected sheet as it appears in the spreadsheet document. It's not the name of the sheet!



In the latest versions you can even specify the Sheet Name by its order, i.e. **#1** is the first sheet, **#2** is the second sheet, whereas **#L1** is the last sheet, **#L2** is the second to last sheet and so on.

Exporting tables and data from an Excel document

At some times you may not want to import data directly from an Excel file. One reason might be that you want to process them before importing them with Tabulizer. In such case, you need to export the data from Excel using the old-fashioned way: The CSV plain text format.

To do so, save the stylesheet that contains the data you want to convert as a CSV text file (a.k.a. Comma Separated Values). Choose as column separator/field delimiter one that is supported by the Tabulizer plugin, like the comma (,) or the semicolon (;). Use double or single quotes as your text separator/delimiter.

Exporting tables from a Word document

Depending on the application/version you are using the following procedure may differ.

a) Microsoft Word 2007:

1. Select the rows or table that you want to convert to paragraphs.
2. Under Table Tools, on the Layout tab, in the Data group, click Convert to Text.
3. Under Separate text at, click the option for the separator character (separator characters: Characters you choose to indicate where you want text to separate when you convert a table to text, or where you want new rows or columns to begin when you convert text to a table.) that you want to use in place of the column boundaries.

b) Microsoft Word 2003:

1. Select the rows or table that you want to convert to paragraphs.
2. On the Table menu, point to Convert, and then click Table to Text.
3. Under Separate text with, click the option for the separator character (separator characters: Characters you choose to indicate where you want text to separate when you convert a table to text, or where you want new rows or columns to begin when you convert text to a table.) you want to use in place of the column boundaries.

c) OpenOffice Writer:

1. Click inside the table.
2. Select the menu Table → Convert → Table to Text

Data Sources for tables with dynamic content

Sometimes you want to create a table from an external source, let's say an Excel file. If this is one-time operation, then you can create the table normally, by clicking on the Tabulizer editor button invoking the Tabulizer dialog box to fill out the Excel importation parameters.

But what if this external file changes frequently and you want these changes to propagate to your website? In this case, it's better create a **data source** that is associated with the Excel file and link your table with that data source. With Tabulizer 4.0 you can create data sources that are associated with the following external/internal content types:

1. Excel files
2. CSV/Text files
3. HTML/XML files or other webpages
4. Database queries
5. Wordpress posts (articles)


The following paragraphs show you how to create a new data source, so every time an excel file changes that linked table is updated as well.

How to create a new data source

From the **Tabulizer** menu click on the **Data Source** submenu.



Then click on the **New Data Source** button.



In the form that appears set the Source Type field to “Excel File”. When you do that the Source Param(eter)s list will get updated to reflect the selected source type. The File path/URL parameter should point to the actual location of the Excel file. This location can be:

- A file path (directory) if the file is on the same server as the Wordpress site,. e.g.
/home/tutor/public_html/tmp

- A web address (URL) if the file is on another website, e.g.
<http://myothersite.com/files/sales.php>


Of course, for the second option to work (URL) you need to have enough permissions to read a file from another web site.

The other parameters are the same as the ones mentioned in the section about [how to import data from an Excel file](#).

You also need to select the ruleset that you want to be applied to the produced table.

Data Source Cache: In order to improve performance, you can choose to enable caching for a certain period of time (measured in minutes). This will be very useful, if your source does not change very frequently and it takes some time for accessing its contents (e.g. a remote web page). When you save the data source the cache contents get cleared automatically.

Once you have created a data source you can simply add it to any post/page using the corresponding editor button as shown in the image below:



Add more flexibility with data source variable parameters

Starting with version 4.1 the data sources parameters can contain variables that get their value in one of the following ways:

- Wordpress editor
- HTTP Request (GET/POST)
- Logged in User/System environment

For example, let's define a data source that is linked to the following database query:

```
SELECT * FROM # shop_orders WHERE user_id = {user_id}
```

The `{user_id}` will be replaced by the user id of the logged in user. As a result, the data source will contain different data and each user will see a different table view in the front-end that contains data specifically for him. Here is a list of variables you can use while constructing your data source:

- `{user_id}`
- `{user_name}`
- `{user_email}`
- `{user_fullname}`
- `{user_lastvisit_date}`
- `{user_register_date}`
- `{user_groupids}`
- `{site_lang}`
- `{current_datetime}`

You can also use the following custom variables:

- {user_param_ID_url:DATA_TYPE}
- {user_param_ID_editor:DATA_TYPE}
- {user_param_ID:DATA_TYPE}

ID is an integer value (i.e. 1,2,3, ...)

DATA_TYPE can be:

- int: integer
- float: float, real, decimal
- date: date
- cmd: can contain latin letters (a-z), numbers (0-9), the underscore (_), the period (.) and the hyphen (-).

Here are some examples:

{user_param_1_url:int}, {user_param_2_editor:cmd}, {user_param_10:float}


When trying to assigning a value to these user defined variables, the following rules apply:

- {user_param_ID_url:DATA_TYPE} can take the value only from the GET/POST request
- {user_param_ID_editor:DATA_TYPE} can take the value only from the editor.
- {user_param_ID:DATA_TYPE} will take the value from the editor, and it will be overwritten by the GET/POST value, is present. In other words:
 if {user_param_ID_url:DATA_TYPE} is specified {user_param_ID:DATA_TYPE} =
 {user_param_ID_url:DATA_TYPE} else {user_param_ID:DATA_TYPE} =
 {user_param_ID_editor:DATA_TYPE}

Let's look at a specific example. We want to create many tables with a sales report for each region of our company. The sales data are contained in the database and the database query looks like this:

```
SELECT * FROM #__sales WHERE region_id = {user_param_1:int}
```

Instead of creating a separate data source for each region, we have created one parametrized query with one user parameter of type integer {user_param_1:int}. The value of this parameter can be specified in the Wordpress editor and/or in the GET/POST request. If it is defined in both places, the value from the GET/POST request will prevail as it has higher precedence.



When we click on the Data Sources editor button the above popup will appear. In the Optional Parameters input box we can write the user defined variables as follows:

ID:VALUE^ID:VALUE^ID:VALUE^....^ID:VALUE

ID is the ID of the user variable and VALUE is it's value. If you have more than one you can separate them with the ^ symbol.

In the figure above the **1:23** means, ID=**1** VALUE=**23** and the value of {user_param_1.int} will be replaced with **23**. The resulting query will be:

```
SELECT * FROM # __sales WHERE region_id = 23
```

We can repeat the same process for all other region ids, so with a single data source we have covered all regions instead a creating a separate data source for each region.

If you want to provide the values for the user defined variables from the GET/POST request, use the **data_source_user_params** variable, which is similar to the "Optional Parameters". For instance, in a page that contains the data source in our example, we can overwrite the editor's value by calling the page with the following url:

http://mysite.com/index.php/9-regional-sales?data_source_user_params=1%3A23

1%3A23 is the url encoded value of 1:23.

Tip: You can also use the following **shortcode**, which is useful where there is no other option:

[datasource tag="xyz"] (without user parameters)


[datasource tag="xyz" user_params="abc"] (with user parameters)

Convert your tables into graphs


Tabulizer allows you to convert a new or an existing table into an interactive graph. That fact that

the produced graph is not a plain static image means that it's lighter to download that has some extra features, like animation, zooming, highlighter, etc. These are the graph type you can create:


Line




Candlestick




Bar



Bubble



Pie



Donut



Meter Gauge



Before converting your tables into graph you need to create first a graph ruleset and contains all these preferences (graph type, colors, input rows, etc) that will be used for the conversion.

Create a graph ruleset – Basic Example


A graph ruleset is a regular Tabulizer ruleset that contains only one rule which specifies how the table-to-graph conversion should take place. What this means is that it can be combined with other rules (i.e. calculations and formatting).

For the time being, in order to create a graph ruleset you have to use the online graph creation wizard available at www.tabulizer.com. For this example, we will create a simple 1-series line graph. Here are the specifications:

Graph Type	Line
Number of Series	1
X-Axis	Row 1 of input table
Y-Axis	Row 2 of input table

Step 1

Go to www.tabulizer.com and from the top menu “Rulesets” select the submenu “Graph Creation Wizard”.



Leave the preselected values for Graph Type (Line) and Number of Data Series (1). When ready click on the **Next Step** button.

The screenshot shows the configuration interface for creating a graph. On the left, there are two sections: 'Graph Type' and 'Number of Data Series'. The 'Graph Type' dropdown is set to 'Line'. The 'Number of Data Series' dropdown is set to '1'. To the right of these settings is a line graph visualization showing a single data series with 10 data points. The x-axis is labeled from 0 to 10, and the y-axis is labeled from 0 to 10. The data points are connected by a blue line. At the bottom of the interface is a 'Next Step' button.

Step 2

In this step you are asked to specify all the preferences that you want the graph to have. In our basic example we no particular preferences other than the data sources for the graph (row 1 → X Axis, row 2 → Y axis).

Make the changes as shown in the figure below and when ready click on the **Next Step** button.

Graph Data/Series

Graph Series #1 [Hide Options]

Series Display

Show Serie

Label

Color

☒ Yes | ☐ No

Data Values/Y Axis

Element

Range

Element Section

Data Type

Table Row

2

Auto

Data Labels/X Axis

Element

Range

Element Section

Data Type

Table Row

1

Auto

Step 3

In the final step you get the chance to see a preview of the graph and the corresponding sample table input. Fill in the “Ruleset Title” and “Ruleset Description” field and click the **Download Ruleset** button to save to your local disk the generated graph ruleset.

PREVIEW RULESET

SAMPLE INPUT TABLE

48	15	23	70	7	44	25	21	61	55
33	47	69	20	81	95	40	62	52	61
33	52	82	93	58	12	55	88	74	14

Note that only the first two rows of the input table will be used for the graph conversion, the rest of the table rows will be ignored.

After importing the downloaded ruleset archive, we can use it in our Wordpress site. So, let's say we have an article that contains the following table (Average annual travel expenditures by age):

Under 25	25-34	35-44	45-54	55-64	65 and over
400	700	950	980	985	1050

Notice that the first row contains the X-Axis labels and the second row contains the Y-Axis values.

In order to convert this table into graph we move the cursor inside this table and then we click on the **ReTabulize!** Button. When the Tabulizer dialog window pops up we select as our ruleset archive the one we created with the graph creation wizard (note: it contains only one ruleset which is selected by default). Click Convert and Insert, like you would do with any other case.

The produced code should look like this:

```
{tabulizer:graph[rs_xxx54a2y.xml]}
```


```
Under 25 25-34 35-44 45-54 55-64 65 and over
```

```
400      700   950   980   985   1050
```

```
{tabulizer:hpar}
```

As you can see that table is wrapped around the special Tabulizer tags `{tabulizer:graph[rs_xxx54a2y.xml]}` and `{tabulizer:hpar}`. You could add them directly, without going through the ReTabulizer process, if you remembered the filename of the downloaded ruleset archive (though, in the tag you have to replace the extension zip with xml).

When you edit the article you see only the table data and the graph tags. The graph will appear in the front side of the website, as shown in the figure below:



Tip: The table data can be edited any way you like, including adding new columns. Just make sure you don't delete the Tabulizer's graph tags around the table.

Using more options to adjust your graph

In the previous paragraphs a simple graph was created to demonstrate the basic use on the online graph creation wizard. In reality you will be using much more options and features to bring the produced graph closer to your actual needs. For instance, you will probably add a graph legend,

change the colors, put a label on your data series, add trendlines, change the format of the X-Axis and so on.


Let's try to create a new graph ruleset with a few more options that will be used for the same input table (Average annual travel expenditures by age):

Under 25	25-34	35-44	45-54	55-64	65 and over
400	700	950	980	985	1050

We go back to www.tabulizer.com and go to Graph creation wizard, only this time we make the following selections:

Step 1	
Graph Type	Bar
Number of Data Series	1
Step 2	
Graph Data/Series	Serie Display/Label: Annual travel expenditures Serie Display/Color: #d99694 Value/Element: Table Row Value/Range:2 Trendline/Add Trendline:Yes Trendline/Color:#c0504d
Graph Axes/X Axis	Show Axis/Label: Age groups Axis Tick Labels/Element: Table row Axis Tick Labels/Range: 1
Graph Axes/Y Axis	Axis Tick Labels/Prefix: \$
Graph Options	Legend Display/Show Legend: Yes

This is the how the new graph looks like:



User Preferences

If you are using the same ruleset again and again you might find very useful to set the user preferences so it gets preselected every time you invoke the Tabulizer dialog box.

To access the preferences panel, from the **Tabulizer** menu select the **User Preferences** submenu.

The screenshot shows the WordPress dashboard with the 'Tabulizer' menu item selected in the left sidebar. The 'User Preferences' panel is open, displaying various settings for the Tabulizer plugin. The settings are organized into sections: 'Tabulizer Dialog', 'Excel Reading Preferences', 'Data Source Preferences', 'Archive Help', 'Email cloaking', 'Datables Preferences', 'Scroll Library Preferences', and 'Safe Mode'. Each section contains specific configuration options, many of which are pre-selected or have default values. A 'Save' button is located in the top right corner of the panel. The bottom of the page features a WordPress notice and the version number 'Version 4.1'.

In the form that appears select the desired ruleset archive and ruleset name and click on the **Save** button to keep the changes. You can also set the default column separator, text enclosure and column consistency.

Status – Tabulizer, Wordpress and System Information

Sometimes it's useful to have a quick view of all the basic parameters that may affect the use of Tabulizer. For this reason, you can go to Tabulizer's panel (menu Components → Tabulizer) and click on the **Status** button.

When you contact the technical support to report an issue, it's always a good idea to include the information found on this page.

Posts

Media

Links

Pages

Comments

Appearance

Plugins 1

Users

Tools

Settings

Tabulizer

Ruleset Archives

Data Sources

User Preferences

Permissions

Status

Help

Collapse menu

Status

Tabulizer

Tabulizer Version	4.0.18
-------------------	--------

Wordpress & System

Wordpress Version	3.3.1
PHP Version	5.3.1
PHP MBString Library	Yes
PHP ZipArchive Library	Yes
PHP XML Parser Library	Yes
Directory Permissions	Directory C:\Apache2.2\htdocs\temp\ Directory C:\Apache2.2\htdocs\temp\ Directory C:\Apache2.2\htdocs\temp\ Directory C:\Apache2.2\htdocs\temp\ Directory C:\Apache2.2\htdocs\temp\ Directory C:\Apache2.2\htdocs\temp\
PHP Memory Limit	256M
PHP Upload Max Size	5M
PHP Post Max Size	8M
PHP Magic Quotes	No

Troubleshooting common issues

Please read this tutorial thoroughly before contacting us or sending a bug report. Below we describe the most common problems and their resolutions.

Issue #1: Unable to insert the produced HTML code into the article.

Cause 1: Tabulizer has been tested with the default Wordpress editor (TinyMCE) and other popular editors available for Wordpress. Nevertheless, it is possible that some new editor is not compatible with Tabulizer or it's not working as expected.

Resolution: Switch back to TinyMCE or some other compatible editor before clicking on the Tabulize! button.

Cause 2: Tabulizer uses Ajax and jQuery technology to transfer data between server and client as well as between browser windows. If your browser is not 100% compatible with these technologies, or if there is a conflict with another Javascript library that is included in your specific Wordpress environment, the Tabulizer popup may become unresponsive.

Resolution: Use a different web browser (preferably Firefox).

Issue #2: The produced table does not appear as expected

Cause 1: Any table produced with the Tabulizer uses CSS selectors for styling. What does this mean is that in order for the table to have the proper appearance, all **the required CSS files should be included**.

Resolution: Make sure that the required CSS files are included in your Wordpress site. You can view the source code of any page to verify that.

Cause 2: If you have checked cause #1, and you have made sure that all required CSS files are included, there might be a **conflict between the definition of the CSS selectors used by the Tabulizer rulesets and the Wordpress's active theme**. When the same CSS selector is defined multiple times, a CSS precedence takes place that controls which CSS rule applies to a given HTML element. For instance, if you have defined that CSS selector `first_row` should have a blue background, but somewhere else the `first_row` is defined again with green background, the definition with the higher specificity will take precedence.

Resolution: Try to increase the specificity of Tabulizer's CSS files, so they have higher precedence. For instance, the `table.class_table tr.class_tr td.class_td {}` has higher specificity than `.class_td {}`. Another thing to look is the use (or misuse) of the exclamation mark (!) that affects the normal CSS selector precedence.

Issue #3: Rulesets are missing or have different rules and attributes

Each ruleset should have a unique name and title. In other words, no two rulesets can have the same name even though they belong to different ruleset archives (files).

Resolution: Use Tabulizer component to verify that all rulesets are valid and there are no conflicts in their definition. With the Tabulizer component you can browse all available rulesets, view their rules and preview their styling outcome with sample data. Avoid editing ruleset archives directly with a text/xml editor as this is more error prone.

Issue #4: Unable to import rulesets, write files or create folders

When you import a ruleset archive or when you install the Tabulizer application you may get a “file error” message.

Resolution: Most of the times this is a file permission error. Linux operating system is using file permissions for security purposes, so when a user does not have access to a folder created by another user a file permission error occurs. So, if some folders/files are owned by the Apache user (because Wordpress is running as Apache) and some other and owned by the FTP user (because you copied all Wordpress files via FTP) this issue may arise. Please contact your web hosting provider and explain this problem and ask for a resolution. Most web hosting companies are able to handle it.

The other explanation is that the ZipArchive library is missing or it's not enabled. If that's the case you need to contact your system administrator to enable this feature for you (Hint: In order to use the missing zip functions you must compile PHP with zip support by using the --enable-zip configure option).

Other “last resort” solutions:

- 1) Unzip the ruleset archive locally.
- 2) Copy the css/rules folders via FTP to *{wordpress root directory}/wp-content/plugins/tabulizer/templates/tabulizer*.
- 3) If needed, change the file permission settings temporarily (set to 0777) and when done revert settings to their original values.

Issue #5: Internal Server Error (500)

When you invoke the Tabulizer while editing your article, in the popup window appears a “500 Internal Server Error”.

Resolution: This means that one or the required PHP libraries is missing or a file access restriction is in place.

If there is a missing PHP library, then you need to examine the PHP error log file and look at the last error to get a clue. If you can't find the error log file, check if the following libraries/extensions are enabled:

- **MBString** (mbstring extension)
- **ZipArchive** (zip extension)

If it is a file restriction case, then you need to examine anything that could cause that. For example, some site for security purposes have installed an **.htaccess** file that prohibits that access to certain files or folders. The presence of a **SEF (Search Engine Friendly) extension** may also be responsible for such behavior.

Issue #6: “The number of columns must be the same on each row” error message

Please read the paragraph on column consistency in **Creating a table with Tabulizer**.

Issue #7: Magic quotes are on, causing slashes to be added automatically in front of double quotes (\")

Magic quotes was a security tool of the past that in PHP v5.3 became deprecated and in PHP v5.4

was removed completely. It is recommended that you set the magic quotes to OFF, unless there is a special requirement by another PHP application, Ask your system administrator to change this setting.

Issue #8: HTML links and other elements are removed or set to “undefined” when I click the insert button

TinyMCE, the default Wordpress editor, may have enabled some plugins that do “filter” everything you insert into the article/content. If you are suspecting that TinyMCE (or another Wordpress editor) is messing up the HTML code you insert by Tabulizer, you can try to set your switch editor and see what is happens. If that's the case, you can try to use another Wordpress editor or disable the “insert filtering” mechanism.

Issue #9: Strict error reporting (E_STRICT) is causing error messages similar to “Strict Standards: Only variables should be assigned by reference in ...”

If the error reporting mode of the PHP language is set to strict, you may experience error messages during the installation phase or later on. Since, this has to do with PHP it will affect not only Tabulizer and other Wordpress plugins, but everything that runs on PHP as well. In the php.ini file your current settings most likely include the line `error_reporting = E_ALL | E_STRICT` meaning the system is reporting as errors plain notices.

The E_STRICT flag is used by developers, it is an overkill for regular users and a bad practice for "live sites".

Issue #10: Fix for “datatables warning (table id): Requested unknown parameter X from the data source for row Y”

Some Tabulizer's advanced features are making use of a very powerful javascript library called “Datatables”. One of them is the client-side table sorting, but there are others as well. Datatables don't like cell merging, because generally speaking they expect the same number of cells on every row. For this reason if a cell is empty and `autospans` is active, cell merging will occur giving the “*DataTables warning (table id): Requested unknown parameter X from the data source for row Y*” error message. In order to solve this issue you need to remove any rules that have the `autospans` property set to true.

Issue #11: Fix for “MySQL server has gone away”

Tabulizer is using caching for some operations, including the data sources when cache is enabled. If cases where the linked file is very large and the produced table is over 1MB, it is possible that you will get a “MySQL server has gone away” error message. This is due to the fact that the query that is storing the produced HTML to the database is over 1MB as well and if the maximum size of the query is 1MB (or less) the connection to the database server is lost. In order to resolve this issue you need to increase the packet size of your MySQL by adjusting the appropriate parameter in the MySQL configuration file, similar to:

```
[mysqld]
```

```
max_allowed_packet=16M
```

Getting more help and updates

For more sample rulesets, tutorials and software updates please visit <http://www.tabulizer.com>